



HOME OF PELICAN ISLAND  
BUILDING DEPARTMENT  
1225 MAIN STREET • SEBASTIAN, FLORIDA 32958  
TELEPHONE: (772) 589-5537 • FAX (772) 589-2566

## **WATER SERVICE INSTALLATION**

### **PIPE:**

- Minimum ¾" I.D. (inside diameter)
- Sch. #40 PVC or copper
- Recommended 12" below grade

### **SHUTOFF:**

- Must have an accessible valve between house and meter.
- Valve must be "full flow" ie: ball valve or gate valve.

### **CONNECTIONS:**

- Water service cannot be connected in any way to pipe that is also connected to a well.

### **DRAIN FIELD:**

- Any portion of the water service pipe that is within 10 feet of the drain field shall be sleeved within 1 ½" or larger PVC.

### **HOSE BIBBS:**

- All existing and/or added hose bibs shall have a atmospheric-type or Pressure-type vacuum breaker permanently attached before inspection.

Once you have completed connections, call for a ***final inspection***. You do ***not*** have to wait for this inspection to use the water. Please call 589-5537 one day in advance to schedule a final inspection.